

DIV #6 FRAMING SCOPE OF WORK

- 1) PROVIDE FULL SCOPE DIV #6 ROUGH FRAMING PER PLANS.
- 2) FOUNDATION AND SLAB IN PLACE W/GROUND WORK ROUGH IN.
- 3) ALL STRUCTURAL STEEL WILL BE IN PLACE ALONG WITH STEEL I BEAMS/ BOLTED OR WELDED IN PLACE/BORED FOR TOP PLATE, MUDSILL ANCHOR BOLTS WILL BE IMBEDED NUT W/WASHER PROVIDED.
- 4) FIRST & SECOND FLOOR LUMBER WILL BE STAGED W/USAGE SHEET
- 5) PROVIDE ALL NAILS,GENERATORS,AIR COMPRESSORS,PETTIBONE W/OSHA APPROVED WORK PLATFORM & CRANE
- 6) WMD TO PROVIDE ALL CONSTRUCTION ADHESIVE, HANGERS, CLIPS, WALL STRAPPING, HURRICANE TIES, PLATE TO WALL STRAPPING, GIRDER TRUSS TIEDOWNS, SILL SEALER.

SCOPE OF WORK

- 1) PROVIDE FRAMING LABOR PER DRAWINGS, CONVENTIONAL FLOOR JOISTS W/ ¾" T&G ADVANTECH, EXTERIOR WALLS PER PLAN, HEIGHTS PER PLAN. BALLOON FRAME WALLS TALLER THAN 10', 2X12 HEADERS 3 PLY ALL OPENINGS U.N.O., LVL HEADERS AS NOTED.
- 2) PROVIDE DOOR & WINDOW ROUGH OPENINGS TO SCHEDULE.
- 3) PROVIDE FOR INSTALLATION FOR ALL DOORS AND WINDOWS EXCEPT ALUMINUM STOREFRONT DOORS.
- 4) INSTALL TYVEK HOUSE WRAP RETURN INTO OPENINGS AND STAPLED.
- 5) INSTALL WOOD BLOCKING AT CABINetry & TOILET ACCESSORIES LOCATIONS
- 6) INSTALL ROOF BRACING PER STANDARD CONSTRUCTION PRACTICES
- 7) ROOF SHEATHING 5/8 ADVANTECH W,SPACER CLIPS 2 HURRICANE TIES TO CODE, CONVENTIONAL FRAME ROOF PER PLANS.

- 8) PROVIDE INSTALLATION FOR SILL PLATE TO WALL STRAPPING, STRAPPING AT FLOOR JOISTS, STRAPPING AT ROOF PLATE.
- 9) PROVIDE FOR FRAMING OF TREATED DECK AND INSTALLATION OF COMPOSITE T&G DECKING W/HIDDEN FASTNER SYSTEM.
- 10) W.M.DAVIS TO PROVIDE ALL BULKHEAD FRAMING FOR NEW HVAC DUCT CHASES.